

TECHNICAL RESEARCH CENTER
KING COLUMN DEPARTMENT OF
NATURAL RESOURCES AND PARKS

## HYDROLOGIC DATA REVIEW

for

**King County Solid Waste Division** 

as

Subcontractor to

**Harper Owes** 

7/20/88



#### PURPOSES

1. Review previous hydrologic studies and <u>evaluate and</u> <u>critique</u> without duplicating pre-existing efforts.

2. Evaluate leachate hydrology in terms of quantity, flow variation, and geographic distribution in order to provide flow related <a href="Design Criteria">Design Criteria</a> for Leachate Treatment Design.



### OBJECTIVES

- Identify factors controlling leachate flow:
   percolation boundaries
   seepage to surface
   collection system interfaces
   mounding effects
   flow and pumping through leachate lines.
- Quantify flow magnitudes and variation of leachate.
- Assess chemical characteristics and variation of leachate.



### METHODOLOGY

#### Review exisiting reports

Existing Area Report, Sweet, Edwards & Associates, Inc. December 1985.

Site Development Plan, CH2M Hill, December 1987.

Operations Manual, CH2M Hill, May 1988.

Ground Water Geology/Quality Investigations for the Cedar Hills Regional Landfill, R. W. Beck and Associates, Sweet, Edwards, & Assoc. Dec. 1984


Existing Leachate Interceptor and Collection Facilities Map, Harper Owes, July 1985.

Boring Logs, Sweet, Edwards & Associates, 1983-1986.

 Review and Analyze Rain Gauge, Flow Recorder and Pump Operation Data.

Harper Owes Lotus 1-2-3 database.






# What is the Groundwater Flow Direction in the Deep Aquifer?


- North EAST or North WEST?
- · Has the flow direction been refined further?
- How does flow change as production wells are pumped?
- · Offsite wells being monitored are to the NE, E, SE.
- Could Wells # 18 and # 22 (Parametrix, 1986) be sampled?





RECOMMEDED OFF-SITE WELLS TO BE MONITORED





0 Leachate Collector Trench Clean Outs 26 Depth of Leachate Collection Trench O--- Leachate Collection Trench in Till -O Leachate Collection Trench in Outwash

Approximate Scale in Feet



CEDAR HILLS SANITARY LANDFILL isopach map for the Yashon till, including weathered till. Diagram includes position of leachate collection trench (depth) and location of the geologic sections.

## 

#### Refuse Pile

5.1 X 10<sup>-3</sup> to 5.1 X 10<sup>-4</sup> cm/sec (Sweet-Edwards, 1988)

#### **Vashon Till**

(undifferentiated) 3.6 X 10<sup>-3</sup> to 5.1X 10<sup>-6</sup> cm/sec (Sweet-Edwards, 1984) (weathered) 2 X 10<sup>-6</sup> cm/sec (CH2M-Hill, 1985) (unweathered) 10<sup>-6</sup> to 10<sup>-7</sup> cm/sec (Converse, 1980) 5 X 10<sup>-5</sup> to 7 X 10<sup>-8</sup> cm/sec (CH2M-Hill, 1985)

#### **Stratified Drift**

9.1 X 10<sup>-3</sup> cm/sec to 1.2 X 10<sup>-5</sup> cm/sec (Sweet-Edwards, 1984)

#### **Outwash Deposits**

1.4 X10 cm/sec to 1.9 X 10 cm/sec (Sweet-Edwards)



## **Leachate Head Reduction Study**

**Limitations of the Study:** 

**Mound Morphology** 

Original topographic surface

Piezometric surface

**Spatial Variability Parameters Uncertain** 

 $K_{\vee}$  vs.  $K_{H}$ , storativity

Stratigraphy

Thickness of leachate

Wells are aligned N-S

Physical properties of leachate vs. water

Additional pump testing would be beneficial



#### **Leachate Head Reduction Study**


**Analysis of the Conclusions:** 

**Three Design Options** 

- 7 horizontal drains
- 25 vertical wells
- · Combination of wells and drains

Sweet-Edwards considered the effectiveness, cost, and feasibility of all options. Conclusions are reasonable based on assumptions and limitations of the data. However, more data are needed to evaluate and design the system.






#### **Data Limitations**


- Though data collected, precipitation reports not available after March 30, 1988.
- Flow Recorder Data for Manholes available from Dec. 16, 1987 thru March 24, 1988.
- Man Hole 2 has NO weir, therefore flow monitoring data not valid.






## **Precipitation Record**

#### **Daily Precipitation**





# Does Leachate Flow Correlate with Rainfall?






# Examine Factors Which Could Contribute to Variation

knew all this 4 mos ago.

- Different Bubbler Tube after February 3, 1988.
- Bubbler Tube Fouling Readings immediately before cleaning may be different from readings after cleaning.
- Flows from Maintenance Facility and Alcohol Rehabilitation Center.
- Monitoring record may be <u>statistically</u> inadequate.



# Pump Station 1 flows are slightly correlated to rainfall.





# Use T-Test to Determine whether Monitoring Record Is Affected by Changes

T-Test


One	Two	One	Two			
1.103	0.079	0.39	0.22	mean		
0.882	0.191	0.13	0.02	variance		
0.063	0.230	15	15	number of samples		
0.917	0.083					
0.248	0.121	t=		1.7902542867	5	
0.055	0.595	df=		28		
0.350	0.289	At 5 %, t table= 2.048				
0.133	0.333	At 1	%, t table=	2.763		
0.176	0.376					
0.181	0.198	One is MH-7 flow 3-day	s BEFORE Sei	rvicing March, Feb		
0.206	0.192	Two is MH-7 flow 3-days AFTER Servicing March, Feb				
0.282	0.345					
0.831	0.068	With 99% confidence, the	two populati	ions are the same.	TRUE	
0.408	0.057	With 95% confidence, the two populations are the same. TRUE				
0.079	0.086					
		Degrees of Freedom t at 0.05			tat 0.	.01
		1	12.706	•		63.657
		2	4.303	2	2	9.925
		2 3	3.182	7	3	5.841



# Use T-Test to Determine whether Monitoring Record Is Affected by Changes

1-100

	Ore	1wc	Ore		Iwc				
ı ı	1.103	0.0/9	0	<b>59</b>	0.22	mear			
	0.882	0.191	0	13	0.02	var.srce			
	0.063	0.230		15	15	rumber of samp e	S		
	0.91/	0.083							
	0.248	0.121		t-		1./90254286/	13		
				cf-		28			
	0.350	0.289			%, t tab e-				
	0.133	0.535		At i	×, ttab e−	2 /63			
	0.1/6	0.3/6							
	0.181	0.198	Ore sMH-/fcv	v S-csy	S BEFORE Se	rv cing March, Feb	,		
	0 206	0.192	I WC 'S MH- / f C'	W S-CZ	VS AFIER Ser	vicing March, Feb			
	0.282	0.343				•			
	0.831	0.068	With 99% confice	erce.the	two cocu at	ors are the same.		IRUE	
	0.408	0.05/	W'th 95% conficence, the two populations are the same. IRUE						
	0.079	0.086							
			Degrees of Freed	m t at	0.05			t at 0.01	1
				3	12./06		1	6.	3.65/
				2	1 303		2	1	9.925
				3	3.182		5		5.841
1									



- 1 The two groups are independent.
- 2.Measurement is at least at the interval level.
- 3. The populations are normally distributed.

"Severe departure from normality seems to have little effect on the conclusions when sample sizes are 30 or more." Sharp, Statistics for the Social Sciences, p.275.

- 4. The populations have the same variances.
- 5. The samples are drawn at random.

#### **T-Test Results**

- Precipitation BEFORE and AFTER Bubbler Port Change (Feb. 3, 1988)----> SAME Population.
- MH-11 flow BEFORE and AFTER Bubbler Port Change----> DIFFERENT Population.
- MH-7 flow BEFORE and AFTER Bubbler Port Change----> DIFFERENT Population.
- MH-5 flow BEFORE and AFTER Bubbler Port Change-----> SAME Population with 99 and 95% Confidence.



# Does Flow Monitor Servicing Make a Difference?

Possibly so but not enough data to say conclusively.

MH-7 Flows 3 days before servicing and 3 days after servicing in February, March of 1988.

T-Test----> Populations are the Same (95% and 99% confidence)

	<b>Before</b>	After
n	15	15
mean	0.39	0.22
variance	0.13	0.02

